



**THE DATASHEET OF
EHF-4BE5250**



Messrs. Digi-Key

Issue No. : PC-04-006
Date of issue : March 2, 2004
Classification: New

Product Description	: Balun
Product Part Number	: EHF4BE5250
Applications	: Cellular phone
	For other applications, contact the undersigned in advance.
Term of Validity	: Five years from the date of issue.

Delivery Specification

Receipt Used Column

MATSUSHITA ELECTRONIC COMPONENTS CO., LTD. MODULE DEVICE COMPANY MODULE BUSINESS UNIT 992-1 AIBA OHNO-CHO IBI-GUN GIHU PREF 501-0598 JAPAN TEL +81-585-36-2345 FAX +81-585-36-2353	
Communication Module Business Group	Prepared by : H. Ito Authorized by : M. Mizuno






[Manufacturing section]

Final Production Plant	(Name) MATSUSHITA ELECTRONIC COMPONENTS CO., LTD. (Address) 992-1 AIBA OHNO-CHO IBI-GUN GIHU PREF 501-0598 JAPAN
Final Inspection Plant	The same as above

[Shape, appearance, dimension] Unit: mm

<Top view>

<Bottom and side view>



Weight of the individual component: 3mg

Note 1) "typ" is used where no dimensional tolerance applies.

Item	Description
Appearance/ construction	Product surface shall be covered with a protective film, which does not easily separate nor present noticeable unevenness, scratches, pinholes, color changes etc.
	Terminals shall ensure practically acceptable quality
	Substrate shall be as shown in the drawing with no excessive chippings, scratches, burrs, or cracks.
Marking	Shall be legible in black (with printing paste)
Remarks	■ marked side for pin 1

Balun		Delivery Specification			EHF4BE5250 Appearance
Enact. Date March 2, 2004	P.S.M	Approval	Check	Plan	
Enfo. Date March 2, 2004	-----	M. Mizuno	M. Mizuno	H. Ito	Drawing No. 151-EHF-4BE5250 9-1

[Absolute maximum ratings]

No.	Item	Symbol	Rating	Unit	Remarks
1	Maximum input power	Pmax	100	mW	DC bias must be 0V
2	Operating temperature	Topr	-30...+85	degC	
3	Storage temperature	Tstg	-40...+85	degC	


Note: This component cannot apply a DC Bias.

[Electrical characteristics]


T=-30...+85degC

No.	Item	Test Circuit	Specification			Unit
			Min.	Typ.	Max.	
1	Frequency	-	5150	-	5350	MHz
2	Insertion loss (Back to back)	Fig-2	-	-	1.2	dB
3	Unbalance impedance	-	-	50	-	ohm
4	Balance impedance	-	-	100	-	ohm
5	Unbalance port VSWR	Fig-1	-	-	2.0	-
6	Amplitude balance	Fig-1	-1.5	-	1.5	dB
7	Phase balance	Fig-1	165	180	195	deg

[Internal circuitry]



[Measuring circuit]



< Phase balance measurement >


•Phase1
A=IN, B=OUT, C=Terminal resistor (50 ohm)

•Phase2
A=IN, C=OUT, B=Terminal resistor (50 ohm)

•Phase balance
Phase balance=Phase1-Phase2

< Insertion loss measurement >

Assuming the loss as "Loss" when D=IN, E=OUT
Insertion loss for a device is "Loss"/2



Balun

Delivery Specification

EHF4BE5250

Enact. Date March 2, 2004

P.S.M

Approval

Check

Plan

Specification and measurement

Enfo. Date March 2, 2004

M. Mizuno


M. Mizuno

H. Ito


Drawing No.
151-EHF-4BE5250 9-2

[Terminal dimensions] Unit: mm

<Bottom>




[Recommended PCB pad dimensions] Unit: mm




Balun		Delivery Specification			EHF4BE5250 Terminals/Recommended lands
Enact. Date March 2, 2004	P.S.M	Approval	Check	Plan	
Enfo. Date March 2, 2004	-----	M. Mizuno	M. Mizuno	H. Ito	Drawing No. 151-EHF-4BE5250 9-3

[Quality characteristics]

Test item	Test condition	Judgment criteria
Temperature cycling	-40...+85degC, Each 30 min., 200cy	No abnormality shall be observed in appearance or electrical characteristics
High temperature	+85degC, 1000h	
High-temperature high-humidity storage	+85degC, 85%RH, 1000h	
Low temperature	-40degC, 1000h	
Vibration	0.35mm 10-55Hz, 50m/s ² 55-500Hz	
	10-500-10Hz/11min., in each direction of XYZ, 2h	
Shock (Drop)	1.8m, 6 facesx3cy(with 100g Dummy Load)	
Soldering heat resistance	Reflow: 260degC peak, 3 times	
Electro static discharge	200pF, 0 ohm, +/-200V, Each 3 times	
Solder ability	Solder bath: 230+/-3degC, 3 sec.	Over 95% of the terminal surface shall be covered with solder
Board warping	FR-4(t=1.0mm), 45+/-2mm span, 5+/-1sec. 1mm step, 2mm 	There should not be any cracks in the component or solder joints, no abnormality in electrical characteristics.
Terminal removal	Solder a component on a PC board using the recommended condition shown below and then press the component sideways at 1mm/sec. Destruction limit 4.9N or greater.	
Seating plane co-planarity	Within 0.1mm	

< Recommended soldering condition >

Diagram1 Shown below is a recommended reflow soldering condition



Balun		Delivery Specification			EHF4BE5250 Quality Characteristics
Enact. Date March 2, 2004	P.S.M	Approval	Check	Plan	
Enfo. Date March 2, 2004	-----	M. Mizuno	M. Mizuno	H. Ito	Drawing No. 151-EHF-4BE5250 9-4

[Cautions for use]

- (1) Operating a product over the maximum rating for even a moment may result in a product failure or breakage. Never use a product in such a condition that it may cause a safety problem.
- (2) Opening or short-circuiting the product terminals or inserting a product in the reverse orientation while power is being supplied may cause a breakage. Always avoid such circumstances.
- (3) Operations in a corrosive gas atmosphere or improper environments such as high-temperature, high-humidity or dewy conditions may lead to product performance deterioration, a breakage, a change in appearance etc. Please avoid such conditions, as they are unsafe.
- (4) Always ground the soldering iron or soldering bath used for assembly operation to avoid any excessive voltage applied to a product.
- (5) After soldering with solder bridges, incomplete soldering or in the reverse orientation, supplying power may result in a product breakage. Please confirm the soldered condition before supplying power to the product.
- (6) Excessive stress on the terminals may cause a contact failure or performance deterioration. Please use caution.
- (7) Please provide a fail-safe provision in the product you design by taking any failure of our product into consideration.
- (8) This product does not include a DC-cutting device. Application of a DC voltage between the Balance port and the Unbalance port may cause product deterioration or breakage.

* If any question arises about the safety of this product, please contact us immediately with a request for an engineering examination.

[Remarks]





- *1: All of the materials used in this product are those listed as the existing chemical substances based on the "Law for examination and regulation of manufacture of chemical substances"
- *2: The production process of this product does not use any ozone-depleting chemicals (OZC) regulated by the Montreal Protocol.
- *3: Validity of this specification is 5 years from the date of issue, but the validity is considered on going unless any changes are made.

Balun		Delivery Specification			EHF4BE5250 Cautions
Enact. Date March 2, 2004	P.S.M	Approval	Check	Plan	
Enfo. Date March 2, 2004	-----	M. Mizuno	M. Mizuno	H. Ito	Drawing No. 151-EHF-4BE5250 9-5

[Packaging materials]

1. Materials
- 1) Embossed carrier tape (Refer to the attachment)
 - 2) Top tape: Anti-static
 - 3) Packaging box (Refer to the attachment)
 - 4) Packaging tape, carrier-securing adhesive tape

2. Specification

No.	Item	Condition	Remarks
1	Reel outer diameter	Refer to the attachment	
2	Reel inner diameter	Refer to the attachment	
3	Reel inner width	Refer to the attachment	
4	Quantity in a reel	4000 pieces/reel	
5	Taping direction		
6	Top tape attachment position		Tape breaks force. Min. 10N Top cover tape strength. Min. 10N Tape peel force. 0.1...1.0N Tape peel angle. 165...180degree Reel weight. Max 1500g
7	Label attachment position		Indicated Item Pat No., Lot No. Quantity, Maker Country
8	Tape leader part and tape ending part		
9	Missing products	No missing products shall be allowed	
10	Packaged quantity in a box	21 reels/box (Max)	84000 pieces/box(Max)

Balun		Delivery Specification			EHF4BE5250 Packaging specification 1
Enact. Date March 2, 2004	P.S.M	Approval	Check	Plan	
Enfo. Date March 2, 2004	-----	M. Mizuno	M. Mizuno	H. Ito	Drawing No. 151-EHF-4BE5250 9-6


1. Method

- 1) Load products in each cavity of an embossed carrier tape, in the correct orientation, by leaving the product-unloaded part shown in Item No. 8(P9-6) of the packaging specification.
- 2) Heat-seal a top tape in good alignment on the carrier tape.
- 3) After 4000 pieces are loaded and reeled, provide a product-unloaded part at the tape-leader portion. Secure the tip of the carrier tape with a piece of adhesive tape.
- 4) Stack the reels (21 reels max.) and enclose them in a packaging box. Close the flaps with a piece of adhesive tape.
- 5) Provide markings on the packaging box.


< Items to be indicated >

1. Part No.
2. Quantity
3. Lot No.
4. Manufacturer name
5. Country of origin


Marking on the packaging box



Packaging box shape varies with the number of reels enclosed



Reel label





Number of stacking, 21 reels max.

* Insert cushion material in the empty spaces to secure reels

Balun		Delivery Specification			EHF4BE5250 Packaging specification 2
Enact. Date March 2, 2004	P.S.M	Approval	Check	Plan	
Enfo. Date March 2, 2004	-----	M. Mizuno	M. Mizuno	H. Ito	Drawing No. 151-EHF-4BE5250 9-7

Looking for pricing, stock, or lifecycle information?

Click below to explore more details on WIN SOURCE:

-  [View EHF-4BE5250 on WIN SOURCE](#)
-  [Panasonic Information](#)

Optimize Your Supply Chain with WIN SOURCE Solutions

-  Global Sourcing Solution
-  Obsolete Management
-  Cost Control Management
-  Shortage Management
-  Alternative Solution
-  Excess Inventory Management